

Building Your Pool...

This is a general outline for the construction of your pool project. Features not mentioned in here (slides, spas, tile border, sunledge, etc.) will add 2-7 days to this process. **Please be aware that at some points throughout the below tasks, there may be gaps in time where workers are not onsite due to scheduling of necessary inspections, waiting for product to arrive, and other factors involved in the construction of your pool.**

<p>1: PRE-CONSTRUCTION /DIG JOB SITE LAYOUT With our team and possibly any other necessary contractors</p>	<p>ROUGH CONSTRUCTION CREW WORK IS COMPLETE BACKFILLING IS SCHEDULED BY OUR TEAM</p>
<p>ALL SELECTIONS MUST BE FINALIZED AT THIS TIME</p>	<p>18: BACKFILLING OF POOL PERIMETER AND PLUMBING TRENCHES</p>
<p>2: FINALIZE YOUR PATIO /COPING CONTRACT</p>	<p>19: CONCRETE POOL STEPS, SUNLEDGE(S), BENCHES/SPECIAL INTERIOR FEATURES POURED</p>
<p>3: EXCAVATION /DIG DAY</p>	<p>20: SCHEDULE PATIO LAYOUT MEETING WITH DESIGN PROJECT MANAGER</p>
<p>4: POOL STRUCTURE IS ASSEMBLED</p>	<p>21: MEET ONSITE AND LAYOUT PATIO WITH DESIGN PROJECT MANAGER</p>
<p>5: PRE-CONCRETE POUR INSPECTION SCHEDULED</p>	<p>22: PATIO IS FRAMED BY FRAMERS</p>
<p>3-7 DAYS WAIT TIME FOR BUILDING INSPECTOR TO COME & COMPLETE</p>	<p>23: PATIO PRE-POUR INSPECTION SCHEDULED</p>
<p>6: PRE-CONCRETE POUR INSPECTION</p>	<p>3-7 DAYS WAIT TIME FOR BUILDING INSPECTOR TO COME & COMPLETE</p>
<p>7: CONCRETE FOOTING IS POURED AROUND POOL PERIMETER</p>	<p>24: PATIO PRE-POUR INSPECTION</p>
<p>8: CONCRETE FLOOR IS POURED</p>	<p>25: PATIO AND/OR COPING INSTALLED See your separate patio/coping contract for more details. As a reminder, this must be installed by Anchor.</p>
<p>9: POOL INTERIOR MEASURED FOR VINYL INTERIOR</p>	<p>DEPENDING ON YOUR PATIO /COPING SELECTIONS, INSTALLATION MAY TAKE UP TO 7 DAYS TO BE COMPLETED</p>
<p>10: DIAGRAM FOR VINYL POOL INTERIOR PROCESSED & ORDER IS PLACED</p>	<p>26: ELECTRICIAN CONNECTS EQUIPMENT TO FILTER PAD & MAIN PANEL IN HOUSE * Must have access to enter home at this time.</p>
<p>UP TO 3-4 WEEKS FOR MANUFACTURING & DELIVERY</p>	<p>27: IF FENCE IS REQUIRED, INSTALL PRIOR OR AT THIS TIME AT THE LATEST</p>
<p>11: ALL POOL APPLIANCES INSTALLED I.E. skimmers, returns, lights, water features, etc.</p>	<p>28: AUTOCOVER INSTALLED</p>
<p>12: POOL PLUMBING RUN FROM POOL TO FILTER PAD LOCATION</p>	<p>29: POOL INTERIOR PREPPED FOR COMPLETION</p>
<p>13: ELECTRIC RUN FROM POOL TO FILTER PAD LOCATION</p>	<p>30: POOL INTERIOR INSTALLED & POOL FILLED</p>
<p>14: PLUMBING/ELECTRICAL INSPECTION SCHEDULED</p>	<p>31: ALL SYSTEMS STARTED & TESTED FOR PROPER OPERATION + SET UP OF PROGRAMMING & SCHEDULING IN DIGITAL CONTROL SYSTEM</p>
<p>3-7 DAYS WAIT TIME FOR BUILDING INSPECTOR TO COME & COMPLETE</p>	<p>32: FINAL WALK THROUGH & OPERATIONAL INSTRUCTIONS WITH OUR CONSTRUCTION TECHNICIAN</p>
<p>15: FILTER PAD EQUIPMENT INSTALLED</p>	
<p>16: GAS AND ELECTRIC RUNS INSPECTION</p>	
<p>17: PRESSURE TESTING OF ALL PLUMBING LINES AND SYSTEM</p>	

Weather, manufacturer delays, and other acts of God outside of our control may also increase the duration of the construction process outline above. Please note that we are not responsible for the management or direction of other contractors unaffiliated with Anchor Spa & Pool who may be working on your site simultaneously, therefore we cannot be held responsible for any delays created by them.



CONTACT INFORMATION

CUSTOMER SERVICE : (847) 669-2727

If you have questions throughout the construction process please email:
Construction@AnchorSpaAndPool.com

Our Design & Sales Team

Jessica DeMarco

Designer & Project Manager

Email: Jessica@AnchorSpaAndPool.com

Phone: (630) 709-7904

Josh Kamholz

Permit Acquisition & Product Selections

Email: Josh@AnchorSpaAndPool.com

Phone: (815) 540-5107

Tim Hayes

Sales Manager & Construction Team Leader

Email: Tim@AnchorSpaAndPool.com

Phone: (847) 366-6342

Kim Foley

Accounting & Bookkeeping

Email: Accounting@AnchorSpaAndPool.com

Phone: (847) 669-2727 ext. 4